# UNCLASSIFIED

AD 407 587

### DEFENSE DOCUMENTATION CENTER

**FOR** 

SCIENTIFIC AND TECHNICAL INFORMATION

CAMERON STATION, ALEXANDRIA, VIRGINIA



UNCLASSIFIED

MOTICE: When government or other drawings, specifications or other data are used for any purpose other than in connection with a definitely related government procurement operation, the U. S. Government thereby incurs no responsibility, nor any obligation whatsoever; and the fact that the Government may have formulated, furnished, or in any way supplied the said drawings, specifications, or other data is not to be regarded by implication or otherwise as in any manner licensing the holder or any other person or corporation, or conveying any rights or permission to manufacture, use or sell any patented invention that may in any ray be related thereto.

63-44-1 GIIIIIIID

GENERAL DYNAMICS | CONVAIR

Report No. 8926-159

Material - Magnesium - AZ91 Casting

Evaluation of Non-Destructive Inspection Procedures

P. W. Bergstedt, H. C. Turner, W. M. Sutherland

13 March 1957



Published and Distributed under Contract AF33(657)-8926

## GIIIIID

MODEL

PAGE REPORT NO.

Report No. 8926-159

Material - Magnesium - AZ91 Casting

Evaluation of Non-Destructive Inspection Procedures

#### Abstract:

The multi-ribbed framework for the F-102A airplane speed brake door is an AZ91 magnesium alloy casting about 2-1/2 feet wide by 4-1/2 feet long. This complex casting, which essentially is a lattice of thin-walled ribs, is heat treated and aged prior to end use. Since excessive porosity was encountered with a large number of castings, correlations of the casting strengths with the results of dye-penetrant and radiographic inspection were required. As a result of comparisons of tensile strength data with dye-penetrant and radiographic inspections, the following conclusions were drawn: (1) dye-penetrant inspection is inadequate for determining acceptable limits of casting porosity; and (2) x-ray ratings correlated very well with tensile test results. Radiographic inspection thus was considered the more reliable inspection method.

Reference: Bergstedt, P. W., Turner, H. C., Sutherland, W. M.,
"Speed Brake Casting, 3-73673, Evaluation of,"
General Dynamics/Convair Report MP 56-216, San Diego,
California, 13 March 1957. (Reference attached).

ENGINEERING TES	ST LAB	ORAI	WRITE
-----------------	--------	------	-------

GROUP MATERIALS & PROCESSES LAB.

REPORT\_\_\_56-216 

A DIVISION OF GENERAL DYNAMICS CORPORATION

SAN DIEGO

#### TITLE

REPORT NO. 56-216
SPEED-BRAKE CASTING. 8-73673EVALUATION OF

MODEL: F-102A

			the tank	Chic Tes	F. Strong of, Engineering t Laboratories
NO.	DATE	BY	CHANGE		PAGES AFFECTED
	<u> </u>	<del> </del>			
OPM 1412	1.4	500			

PREPARED BY P. W. Bergstedt

PAGE 1"
REPORT NO. 56-216
MODEL F-102A
DATE 3-13-57

#### REPORT NO. 56-216 SPEED BRAKE CASTING. 8-73673 EVALUATION OF

#### INTRODUCTION:

Part No. 8-73673 is a multi-ribbed framework for the speed brake door of the F-102A. The casting is roughly 2 1/2 ft. wide and 4 1/2 ft. long; it is cast from AZ91 magnesium alloy and subsequently heat treated and aged. Although the complexity of the problems associated with the fabrication of these castings can be readily appreciated, many of the parts received at Convair were found to possess an inordinate amount of porosity. This report describes the evaluation tests which were made on three (3) of the castings.

#### **OBJECT:**

To determine the efficiency of dye-penetrant and radiographic inspection as methods of rating casting quality.

#### CONCLUSIONS:

The tensile tests of specimens cut from the castings led to the following conclusions:

- 1. Dys-penetrant inspection cannot be considered an adequate method of determining the acceptable limits of casting porosity.
- 2. As anticipated, X-ray ratings correlated very well with tensile test results. Radiographic testing is much more trustworthy than dys-penetrant examination as a non-destructive test of such porous materials.

#### PROCEDURE:

Three castings, identified by X-ray No., were included in this investigation. After dys-penetrant examination, rough specimen outlines were scribed on the metal in areas which exhibited varying amounts of dys "bleed-out". The parts were then cleaned and marked for sampling as shown in Figures 1, through 3. In all, twenty-nine specimens were removed from the three castings; No. 18 proved to be too small for test purposes and was discarded.

The coupons were machined to standard 0.5-inch gauge width, but the original surfaces were not disturbed along the flat sides of the samples. In the instances where adjoining ribs entered the gauge section, the ribs were simply cut off outside the fillets.

The samples were then inspected and rated by the Process Control Department. The dye-penetrant method requires approval or rejection by an experienced inspector. Thotographs of all of the coupons are shown in Figures 4 through 10; the pictures were taken shortly after the dye-penetrant examination and with the developer coating still intact.

\*

PAGE 2 REPORT NO.56-216 MODELF-102A DATE 3-13-57

#### PROCEDURE: (Continued)

The grading system employed in the X-ray ratings is based upon a series of filmed standards prescribed by ASTM Standard E98-53T. According to this comparison type of evaluation, Grade 1 would be free of defects, Grade 2 acceptable, Grade 3 acceptable but questionable, and Grade 4 would be rejectable. (This type of procedure enjoys wide-spread usage).

No X-rays were taken of coupons removed from the static-test casting - specimens 18 through 29.

Tensile testing was accomplished by the Physical Test Section using the 12,000 lb. Tinius Olsen Machine.

From the broken tensiles, small sections were then cut from the fracture areas and grouped in plastic mounts for polishing - two or three samples per mount. In each case the prepared surface represented an internal portion of the sample, perpendicular to the fracture, and extending 1/4" to 3/8" from the fracture.

#### RESULTS AND DISCUSSION:

The tensile properties and inspection ratings of the coupons are shown in Table I. The "Correlation" column was based upon an overall appraisal of ratings vs. actual properties for each specimen.

The dys-penetrant technique proved to be useful for rejecting material, but the method could not be used in a positive sense - too many spongy samples were apparently acceptable.


Radiographic inspection was much more reliable as a means of estimating acceptable limits of micro-shrinkage. Since X-rays can detect internal voids which are not connected to the surface, the advantage of this method in applications of this type is readily understood and accepted. It is unfortunate that the X-ray examination did not include the group of specimens from the static-test casting.

A study of the photomicrographs disclosed many regions of localized porosity and/or mechanical tears. Each photograph represents only a small portion of a particular sample and often tends to exaggerate the extent of the defects. The economical practice of placing more than one sample in a single plastic mount led to considerable difficulty in producing an even polish on the relatively soft magnesium samples. Consequently, only one photomicrograph is included in the report for each of the described conditions (Figures 11 through 17).

NOTE: This report was prepared from data recorded in Laboratory Record Book No. 910.

		9	Severa	Nor X-4 YED MODERATE		N. J. ANYGO	:	: *	· *		Not X-ANTED MODERATE SEVERE		Severe	*	X Stutente (10-141-1200)	X MADERATE - SEVERE	Wor 4- 44/60 SEVERE(40 041 12 09) & GOOD	MODERATE (Them)	A Mosesara - Stuere	407 K-RAYED	×	Manager Control Land	M-DE EAST (TOEW)	X SLIGHT (TORW)	Not X-Apred	*		MODERATE (101.1.)	Wet A RACED	GAMS 2 63 "ACCOUNTS - GLOSE & "RESERVANCE"	KELLING	
MECHANISA PAPARTISA  PLAST  PRAST  PR	DVE PEN	Accepted	:	٠ ×	••			•	•		<b>*</b>	<b>"</b>	<b>*</b>			×	•	×		*	` 	* *		×	*	<b>*</b>	* —	*	<b>≺</b>	. S. 14.5		
MACCA MACCA 11, 130 12, 500 13, 500 13, 500 13, 500 13, 500 13, 500 13, 500 13, 500 17, 500		,	280 /5		430 1.5	500 2.0	•		800	~	_,		4		_	0.0	•	_				-	1	i	1	i				- 6R1P NOT	3	
	MECHANICA	<del></del>	-	+-	-	-		4		L .								_	15,900 22	16,300 23	17,300 24	20,00 24	17 300 28	18,600 23	18,000 31	17,100 31,	18,100 33	20,200 33	25 00+5/	TESTING TECHNIQ	00000	_

COMPANIA SAN DEDDO



ANALYSIS
PREPARED BY | Bergetedt/Turner
CHECKED BY | W. M. Sutherland
REVISED BY

C O N V A I R
A BIVISION OF SENERAL DYNAMICS CORPORATION
SAN DIEGO

PAGE 4 REPORT NO. 56-216 MODEL F-102A DATE 3-13-57





FIGURE 2. PART NO. 8-73673. X-RAY NO. H7315-1 (@ UPONS 12-17)

PAGE 5
REPORT NO. 56
MODEL FDATE 3-

56-216 F-102A 3-13-57








FIGURE 4. COUPONS 1, 3, 4, & 5. (SHOWING DYE INDICATIONS)





ANALYSIS

PREPARED BY


CHECKEED BY


W. M. Sutherland

REVISED BY

C O N V A I R
A DIVISION OF SENERAL DYNAMICS CORPORATION
SAN DIEGO

PAGE 9
REPORT NO. 56-216
MODEL F-102A
DATE 3-13-57





ANALYSIS
PREPARED BY Bergstedt/Turner
CHECKED BY W. M. Sutherland
REVISED BY

C O N V A I R
A DIVISION OF GENERAL DYNAMICS CORPORATION
SAN DIEGO

PAGE 10
REPORT NO. 56-216
MODEL F-102A
DATE 3-13-57





FIGURE 8. 00UPONS 19, 22, 23, & 24

(SHOWING DYE INDICATIONS)

PREPARED BY Bergstedt/Turner CHECKED BY W. M. Sutherland

REVISED BY

PAGE 11
REPORT NO. 50-216
MODEL F-10-A
DATE 3-13-57



ANALYSIS

PREPARED BY Bergstedt/Murmer CHECKED BY W. ... Sutherland REVISED BY

C O N V A I R
A DIVISION OF GENERAL DYNAMICS CORPORATION
BAN DIEGO

PAGE1 2 REPORT NO.56-216 MODELF-102A DATE3-13-57




FIGURE 10.

COUPONS 27-29

(SHOWING DYE INDICATIONS)




FIGURE 11. "SEVERE" SHRINKAGE POROSITY (SPEC. No.13)

MAG: 100X UNETCHED




FIGURE "MODERATE TO SEVERE" CONDITION (SPEC.No.7)

MAG: 100X UNETCHED

PAGE 14
REPORT NO. 56-216
MODEL F-102A
DATE 3-13-57



FIGURE 13. "MODERATE" CONDITION (SPEC. No. 28)

MAG: 100X UNETCHED



FIGURE 14. "SLIGHT" CONDITION (SPEC. NO. 14)

MAG: 100X UNETCLED




FIGURE 15. "SEVERE-LOCALIZED" CONDITION (SPEC.NO. 24)

MAG: 100X UNLTCHED



FIGURE 16. "MODERATE-LOCALIZED" CONDITION (SPEC.NO. 9)

MAG: 100X UNETCHED




FIGURE 17. "TORN" CONDITION (SPEC. NO. 10) MAG: 100X UNLTCHED